

McMILLAN

Duty Trial of a 40,000,000-Gal.

Duplex Triple Expansion

Worthington Pumping Engine

Mechanical Engineering

B. S.

1909

UNIVERSITY OF ILLINOIS  
LIBRARY

Class

1909


Book

M22

Volume

Ja09-20M





Digitized by the Internet Archive  
in 2013

<http://archive.org/details/dutytrialof4000000mcmi>

DUTY TRIAL OF A 40,000,000-GAL. DUPLEX TRIPLE  
EXPANSION WORTHINGTON PUMPING ENGINE

BY

EUGENE CAMPBELL McMILLAN

THESIS FOR THE DEGREE OF BACHELOR OF SCIENCE

IN MECHANICAL ENGINEERING

IN THE

COLLEGE OF ENGINEERING

OF THE

UNIVERSITY OF ILLINOIS

Presented June, 1909



1809  
M22

UNIVERSITY OF ILLINOIS

JUNE 1, 1909

THIS IS TO CERTIFY THAT THE THESIS PREPARED UNDER MY SUPERVISION BY

EUGENE CAMPBELL MC.MILLAN

ENTITLED DUTY TRIAL OF A 40,000,000-GAL. DUPLEX TRIPLE

EXPANSION WORTHINGTON PUMPING ENGINE

IS APPROVED BY ME AS FULFILLING THIS PART OF THE REQUIREMENTS FOR THE

DEGREE OF BACHELOR OF SCIENCE

*J. C. Thorpe*  
Instructor in Charge

APPROVED:

*L. P. Brackmidge*  
HEAD OF DEPARTMENT OF MECHANICAL ENGINEERING

144878



## Table of Contents

	page
Introduction	2
Part I. History of the development of the Pumping Engine	3
Part II. The Development of the Henry R. Worthington Pumping Engine	8
Part III. Results of previous tests of Worthing Pumping Engines	13
Part IV. Report of test on Engine E 2025 in the Springfield Avenue Pumping Station of Chicago	15
Part V. Conclusions	23
Log of Indicator Cards	31-34
Engine Log No. I	35-37
Engine Log No. II	38-40
Log of Condensed steam	41-44



## Introduction

While a pump is a very simple mechanism and does not seem a very important factor in the world's progress, yet when one stops to enumerate the different occupations that can be carried on without the aid of a pump in some form or other, he is at once surprised at the smallness of the figure. Were it not for the pump the live-stock on our farms would perish in the summer, while the city would never reach any great size until fire would claim it as a victim. It is this wide scope of utility that has developed the pump into one of the most important of machines, and without it a great handicap would be placed on every industry.

While the pump is one of the most important pieces of machinery, yet in attaining its present stage of development it has presented to engineers some of the most difficult problems. It is the completeness of the solution of these problems in the design and operation of the Henry R. Worthington forty-million gallon pumping engine installed in the Springfield Avenue Pumping Stations of the city of Chicago, that prompted the presentation of this paper.



## Part I

### History of the Development of the Pumping Engine

Considering modern machinery in its relative importance today, it hardly seems natural that the pumps should be among the last to make its appearance. The history of pumping machinery dates from the year 200 B.C., there being no mention of such machinery previous to that time. In early days the man who had a water supply in the form of a well was considered wealthy and the manner of drawing the water to the surface was a matter of secondary consideration it generally being accomplished by means of a cord and buckets or some similar means. This perhaps accounts for the fact that in Hero's "Pneumatics" we find the invention of the pump preceeded by that of the slide valve, the spindle valve, the common clack valve, illustrating the application of a metallic piston to a metallic cylinder, and nearly one hundred other inventions.

While it is impossible to give in this brief discussion all of the inventions produced in the development of the pump of today, yet a few of the main steps will be set forth here. The first pump of which we have any record, described in Hero's "Pneumatics" embodies the present principal of valves; i.e., an inlet and outlet valve to a cylinder in which a piston works. The pumps had two cylinders which were single acting, the pistons being connected to a rocker arm so that one piston at a time discharged water into the common discharge pipe. While



the pump had this early date for its birth, yet it was not until the beginning of the seventeenth century that the true principal of its action was understood. Until this time no attempt had been made to discover the reason why water rose upwards under the piston. In the year 1641 the Duke of Florence when pump maker to his Royal Highness, complained that the water would not rise more than thirty two feet. Galileo was applied to for a solution of the problem but failed, and it was a short time after, that one of his pupils, Toricelli, came to the conclusions that atmospheric pressure counterpoised the thirty -two foot column of water. Experiments in 1643 proved his supposition correct, as well as establishing the principal of our present barometer.

At the beginning of the sixteenth century we do not find any very great steps taken in the development of pumps over the simple one of Hero's time. London seems to claim the honor of having the first water works of any consequence. It was in the year 1581 that Peter Maurice was granted a lease to erect an engine within the first arch of the London Bridge, for the purpose of supplying the city with water. His pumping machinery consisted of an undershot waterwheel, connected to pumps; which, when the tide flowed quickly, had a capacity of pumping at the rate of two and one-half million gallons per twenty-four hours.

Perhaps the next step worthy of note, is that of the invention of the stuffing box. All pumps considered so far have been of the single acting type. In the year 1675 Sir Samuel Morland invented the plunger pump, the main feature of



which was the stuffing box. This not only marks one of the main steps in pump design, but it also made possible the steam engine in its present form.

In the year 1732 M. Demour a Frenchman proposed to raise water by putting into rapid motion pipes spreading at the top like a V. This was the first step in the development of our present form of centrifugal pumps. M. Demour in the operation of his pumps placed the apex of the cone of pipes in water and then by revolving at a high rate of speed the centrifugal force overcame gravity, and the water rose in the pipes and was delivered at a higher level.

While pumps of today do not differ materially from those of the sixteenth and seventeenth centuries, yet there is a marked change in the mode of driving them. The mine pumps of an earlier day were run mostly by horse-power and it was not until the latter part of the eighteenth century that steam was used to any great extent to run pumps. The first type of steam propelled pumps was of the shaft and flywheel pattern, where an engine was used to turn the crank on one end of the shaft while the pump was operated from the other, with the fly-wheel between. There was the objection to this type of pump that the delivery was not constant, but fluctuated throughout the stroke. As the piston came to rest at each end of the stroke, the whole column of water must also stop and start with it, and in this manner a great deal of energy was lost. This was practically overcome for the time being by means of an air chamber placed in the delivery pipe which acted as an accumulator storing up and giving out energy during



each stroke of the pump .

Mr. Jonathan Downton of Blackwell London in the year 1825 overcame this feature in another manner on the pumps that were used in the British Navy at that time. He used the shaft and flywheel type of pump but had three pistons working in the one cylinder. The three piston rods telescoped one another and were attached to three separate cranks on the shaft , set at angles of  $120^{\circ}$  . Thus he had one piston rising all the time so that nearly a constant flow of water from the mains resulted. This type of pump was used for many years by the Britons and proved a most successful machine.

The shaft and fly-wheel pump however had its disadvantage in that the power must be transmitted to the shaft and from there to the pump . This was not a very efficient method and attempts were being made to eliminate this feature when Henry R. Worthington came out with his direct connected pump and engine. That is, with the pump piston on one end of the piston rod and the steam piston on the other. In the first pump put out, he did not gain much, if any , in efficiency over the other forms of pumps, due to the fact that full steam pressure was required throughout the entire stroke and thus the expansive force in the steam could not be utilized. While it was inefficient, yet it was in a different manner , and having over come some difficulties, it gave a new line along which to work. This type of pump had been long looked for, but had been rather slow in its development due to the difficulty of obtaining a positive valve motion. This feature was overcome by Worthington on his single cylinder pump , and later in a



much simpler manner upon the duplex pump where the action of the piston of one pump controlled the valve action of the other.

This type of pump with all of its modern improvements is the pump of today as we see it in all of its varied forms. While the shaft and fly-wheel pump is still used in a great many places and the centrifugal pump has its field, yet none of them serve in as many places as does the direct acting type.



Part II  
The Development of the  
Henry R. Worthington  
Pumping Engine.

It is safe to say that no form of steam pump is in such extensive use today as the direct acting steam pump, and when this is traced to its origin, we find it in the mind of one of the laborers on a canal boat. Mr. Worthington was a young man 23 years of age, with no special training, and a common laborer on one of the boats of our inland water-ways . The canal boats in their progress had to go through locks at various points, and as the pumps for supplying water to the boilers were directly connected to the engines that propelled the boat, it made it necessary for one man to pump the water by hand while the engines were idle. This was the time that all of the extra labor was needed to help operate the lock gates etc., so it entered young Worthingtons mind to make the pump automatic.

Worthington received the first patent on his pump in 1841. The pump while crude in some respects was very complete in others. The primary objects for which it was designed was that of automatically supplying water to a steam boiler. The pump and boiler were so arranged together with floats and levers, that as soon as the water level in the boiler fell to a certain point, the pump started up and continued to run until the maximum level was reached, when it was automatically stopped. This form of pump seemed to work perfectly satisfactorily but the automatic boiler supply attachment soon lost favor in that it



proved as dangerous as it seemed reliable. The pump itself was far from perfection . The first objection lay in the fact that the mass of water being moved came to rest at the end of each stroke, and when it was again started, severe strains were brought upon all parts of the pump and piping. Worthington did not loose sight of this point in his search to improve the original, and it was not many years until he placed what is known as the Worthington Direct-Acting Duplex Pump on the market. This pump was much simpler than the single pump in that the action of one piston controlled the valve motion of the other, which insured a positive action and caused one piston to be a half stroke ahead of the other. This latter feature eliminated the straining action on the pump parts , and gave nearly a steady delivery.

With this improvement the direct acting pump came into quite general use for all small work such as feeding boilers. However there was one other point in which this pump was deficient and which prevented its use where any great quantity of water was to be pumped or where fuel was high in price. The pump constructed as it was required full steam pressure behind the piston for the full stroke, for if there was any diminution of steam in volume or pressure at any point in the stroke the pump came to a standstill. This made the pump very uneconomical in its use of steam, as none of the expansive force present would be utilized. This was first overcome by means of a second steam cylinder placed in line with the first, and having a volume about four times that of the first cylinder. The steam was used in the small cylinder, from which it exhausted behind the piston of the larger and was used again. With this improvement and



other small changes in design the direct acting pump was at last placed in position to compete with the rotative pumps which had held unchallenged supremacy in all of the larger pumping plants of the world.

As the size of water-works plants increased the sudden stopping and starting of the column of water being moved grew to be such an important item, that the fly-wheel pumps soon became inadequate. The direct acting duplex pump eliminates this feature so that with the slight aid of an air chamber in the discharge mains. great masses of water may be forced through long mains without the least unnecessary strains. While the direct acting pumps accomplished many things it still was objectionable in that the steam could not be cut off and allowed to expand in the different cylinders. It was nearing the level of the fly-wheel pump in this respect, yet the latter could store up energy in the fly-wheel at the beginning of the stroke and give it out on the last half, thus excelling the direct acting pump in economy. Attempts were made to attach this feature in the form of a flywheel to the direct acting pump, but it was as a rule at the expense of the much desired steady delivery.

The solution of this problem was at last rendered by the son of the inventor of the direct acting pump. The one idea on which he worked was that the indicator card taken from the water cylinder was practically a rectangle, and that to use the expansive force of the steam he must have an excess pressure at the beginning of the stroke which could be stored up and given out as the steam expanded. Were it not stored up the



excess pressure would be transmitted directly to the water plunger which would result in uneven water pressure throughout the stroke, and the disastrous feature of unsteady pressure in the mains would again be introduced. This energy due to the excess pressure at the beginning of the stroke was stored up in what are called compensating cylinders. To the crosshead of the pump are attached two oscillating cylinders so set that when the piston rod is at the center of its stroke the cylinders which turn on trunions, are at right angles to the piston rod. The compensating cylinders are connected through their hollow trunions to an accumulator. The pressure on the plunger in the cylinders is governed by this differential type of accumulator. This accumulator is a vertical cylinder of two different bores. The smaller bore is at the bottom, and is connected to the trunions of the oscillating cylinders by piping. The upper end, which has the larger bore is connected to the air chamber in the delivery mains. In this accumulator is one common piston the one end of which fits the small bore and the other the large bore of the cylinder. The oscillating cylinders piping and small end of this cylinder are filled with water, while the upper end and piping to the air chamber are filled with air. Thus we have the pressure on the plungers in the compensating cylinders is equal to the pressure per square inch in the water mains multiplied by the ratio of the two piston areas in the accumulator.

The action of this new type of "fly-wheel" as it is sometimes called is as follows : During the first part of the stroke while there is excessive pressure in the steam cylinders the plungers of the compensating cylinders are being forced



in so that energy is being stored up. As soon as the pump piston has passed the middle of the stroke, the steam has been cut off in the steam cylinders and starts to expand, while the compensating cylinders are starting to give out the energy that was stored during the first half of the stroke. Tests have shown this type of "fly-wheel" to be perfectly satisfactory. With this one and perhaps most important steps of all in the development of the direct-acting, pumping engine, this type of machine has risen to a position equal if not superior to any. This feature just described is fully covered by the patents in the hands of the International Steam Pump Co. of New York and until it becomes public property, the performance of this pump will probably not be excelled.



# Part III

## Results of Previous Tests of

### Worthington Pumping Engines

Where located	Capacity per 24 hours in million gal- lons	Date	Steam Cylinders	Dimensions of Engine Water Cylinders	Duty in Millions of Foot pounds.
Brooklyn, N.Y.	3	1885	36" x 18" x 26"	17.3" x 26"	113.4 per 112 lbs. coal
New Bedford, Mass.	5	1886	36" x 18" x 26"	24" x 26"	102 " 100 "
Montreal, P.Q.	10	1888	28.75" x 57.5" x 42"	31.5" x 50"	102 " " "
Davenport Ia.	5	1888	21" x 42" x 36"	19.5" x 36"	121.8 " " "
Hampton Eng.	20	1888	27" x 54" x 43"	40" x 43"	106.5 " 112 "
London Eng.	9	1888	27" x 54" x 39.5"	28" x 39.5"	106.5 " " "
Minneapolis, Minn.	30	1890	33" x 66" x 49.7"	32.6" x 49.7"	130.5 " 100 "
Hammersmith Eng.	7	1890	22" x 43" x 48"	19.5" x 48"	116 " " "
Hyde Park Chicago	12	1890	33" x 66" x 49.8"	33" x 49.8"	108.5 " " "
Memphis Tenn.	30	1891	30" x 60" x 48"	27" x 48"	117.3 " " "
Birmingham Ala.	5	1891	28.75" x 57.5" x 50"	19" x 50"	127.8 " " "
Syracuse N.Y.	10	1891	21" x 42" x 36"	27.5" x 36"	109 " 1000 " steam
Nashville Tenn.	10	1891	41" x 82" x 60"	26.5" x 60"	95.6 " 100 " coal
Lowell Mass.	10	1892	25" x 50" x 38"	27.5" x 38"	116.2 " Million B.T.U.
Port Perry Penn.	3	1892	15" x 33" x 57.5" x 37.8"	16.5" x 37.8"	134 " 1000 lbs. steam
Erie Penn.	12	1893	33" x 66" x 49.75"	29" x 49.75"	127.5 " 100.9 " coal
New Haven Conn.	10	1896	18" x 36" x 36"	26" x 36"	108.2 " 1000 " steam
Hampton Eng.	16.5	1896	18.5" x 29" x 45" x 60"	29" x 60"	113.8 " " "
Montreal	12	1908	21" x 33" x 60" x 29.5" x 36"	36" x 36"	177.3 " " "
New York	15	1904	16" x 25" x 46" x 36"	36" x 36"	155 " " "
Central Park Station	20	1903	21" x 33" x 60" x 50" x 50"	34.5" x 50"	161.6 " " "
Chicago Engine #1200	20		(superheat 209° F)		
" " #1201	20		(superheat 87.2° F)		



Central Park Station

Chicago

Engine E 1201	20	1903	21" x 33" x 60" x 50" (superheat 63.4° F)	34.5" x 50"	156.6 per 1000 lbs. steam
"					
" E 1201	20	1903	21" x 33" x 60" x 50" (superheat 71.2° F)	34.5" x 50"	157.1 " " "
" E 1201	20	1902	21" x 33" x 60" x 50" (superheat 126.7° F)	34.5" x 50"	157.0 " " "
" E 1201	20	1902	21" x 33" x 60" x 50"	34.5" x 50"	163.0 " " "
" E 1201	20	1902	21" x 33" x 60" x 50" (superheat 142.8°)	34.5" x 50"	174.7 " " "
" E 1201	20	1902	21" x 33" x 60" x 50" (superheat 154° F)	34.5" x 50"	174.7 " " "



Part IV  
Report of test on Engine  
E 2025 in the Springfield  
Avenue Pumping Station  
of Chicago .

In this section is submitted a report of the duty trial on the forty-million gallon duplex, triple expansion, Worthington pumping engine located in the Springfield Avenue Pumping Station in Chicago.

Object of Trial, - This trial was conducted by Wm. Swanhausser for the Henry R. Worthington Co., Thomas T. Johnston for the city of Chicago and J. C. Thorpe as the disinterested engineer. The object of the trial being to determine the duty developed per 1000 pounds of steam consumed by the engine when operating against a head of not less than 120 feet, with a steam pressure of not less than 140 pounds per square inch at the throttle, the steam being superheated to at least 140 Farenheit. It was also the object of this trial to determine whether or not the pump would deliver 40 000 U.S. gallons per 24 hours under the above stated conditions.

Description of Engine, - The engine was built and installed by the Henry R. Worthington Co., of New York in the year 1904. It is a vertical, duplex, triple expansion, direct connected pumping engine of the high duty type, having six steam cylinders twenty-seven(27) inches forty-two(42) inches and seventy-six (76) inches in diameter ; two double acting , outside packed water plungers forty-five (45) inches



in diameter, direct connected to the steam cylinders all of which have a nominal stroke of sixty(60) inches. The engine is fitted with the Worthington Improved Corliss Steam Valve Gear , and also has the Worthington High Duty Attachment.

The engine is equipped with a surface condenser , located in the pump suction pipe, having a cooling surfacr of eighteen-hundred (1800) square feet. The air pump, having two double acting plungers twenty (20) inches in diameter and a stroke of sixteen (16) inches, is attached to and driven by the main pump.

The following are the principal dimensions of the engine:

Number of cylinders -----	6
Diameter of high pressure cylinders inches -----	27
Diameter of intermediate pressure cylinders inches -----	42
Diamter of low pressure cylinders inches -----	76
Number of water plungers -----	2
Diameter of water plungers inches -----	45
Nominal stroke of all pistons and plungers inches -----	60
Diamter of piston rods ; one 4" ; two 4" ; and one 6" .	
Area of H. P. piston ( sq. in.) -----	566.27
" " I. P. " " " -----	1366.60
" " I. P. " " " -----	4507.31
" " Plungers " " -----	1577.87
Diameter of air piston of accumulator inches -----	42
" " water plunger of accumulator inches -----	11
" " compensating cylinder plungers inches -----	9
Clearance at contact in high pressure cylinder (%) -----	2.0
" " " " intermediate pressure cylinder (%) -----	1.5
" " " " low pressure cylinder (%)-----	1.0
Clear opening through suction valves, each deck (sq. in.)1200	



clear opening through discharge valves, (square inches ) 1200  
 clear opening through suction pipe (square inches) -----1840

Conduct of Trial - The trial was made October 1 and 2, 1908. The trial beginning at 1:45 o'clock P.M. October 1 and continuing for twenty-four hours (24) ending at 1:45 o'clock P.M. October 2.


Throughout the trial readings were taken every fifteen (15) minutes of the steam pressure, receiver pressure, reheater pressure, jacket pressure, and vacuum. At intervals of thirty (30) minutes indicator cards were taken from the steam cylinders.

Indicator cards were taken from only one set of cylinders at a time. During the first six hours of the test cards were taken from the three left cylinders. During the second six hours from the right three cylinders, the third six hours from the left and the fourth six from the right. Crosby inside spring indicators were used. An eighty (80) pound spring was used on the high pressure cylinder, a twenty (20) pound spring on the intermediate pressure cylinder, and a ten (10) pound spring on the low pressure cylinder. The springs were calibrated before the test and were found to be correct. Samples of the cards taken are included in this report.

During the trial the water of condensation from the condenser, and also from the jacket and reheater drains was collected in large barrels and carefully weighed.

The temperature of the water pumped, of the condensed steam and of the superheat were taken at regular intervals throughout the test.

The revolutions were recorded by a counter connected to



the valve motion of the engine,

The pressure in the discharge main was measured with a Bourdon Gauge which was tested with a dead weight tester both before and after the trial and found to be correct. The elevation of this gauge with reference to the Chicago Datum was determined with an engineers level before the trial. The depth of water in the wet well below the Chicago Datum was shown by a dial connected to a float. This apparatus which is used in the every day operation of the plant, was checked up the day before the trial and several times during the trial and found to be correct. The total head then against which the pump works is the sum of the water pressure gauge reading in feet, the elevation of the same gauge , and the reading of the wet-well dial.



## Sample Calculations

- ( 1 ) Average revolution of engine per minute

$$\frac{\text{Total revolutions}}{24 \times 60}$$

$$\frac{25605}{24 \times 60} = 17.77$$

- ( 2 ) Average piston speed-feet per minute = Average stroke

$$(\text{ft.}) \times 2 \times 17.77$$

$$= 5.124 \times 2 \times 17.77$$

$$= 181.964$$

- ( 3 ) Average plunger displacement per revolution (cu.ft.)

$$= \text{Area of plunger (sq.ft.)} \times 4 \times \text{stroke (ft)}$$

$$= (\pi \times 1.875^2 - .0873) \times 4 \times 5.124$$

$$= 224.399$$

- ( 4 ) Average plunger displacement per revolution gallons

$$= 224.399 \times 7.481$$

$$= 1678.5$$

- ( 5 ) Average plunger displacement per revolution (pounds).

$$= 224.399 \times 62.4$$

$$= 14002.5$$

- ( 6 ) Average plunger displacement per 24 hours (cu.ft.)

$$= (3) \times 25605$$

$$= 224.399 \times 25605$$

$$= 5745736$$

- ( 7 ) Average plunger displacement per 24 hours ( gals)

$$= (4) \times 25605$$

$$= 1678.5 \times 25605$$

$$= 42978105$$



$$\begin{aligned}
 (8) \quad & \text{Average plunger displacement per hour (pounds)} \\
 &= (5) \times 25605 \\
 &= 14002.5 \times 25605 \\
 &= 358,533,926
 \end{aligned}$$

$$\begin{aligned}
 (9) \quad & \text{Net work delivered per 24 hours foot pounds} \\
 &= (8) \times 123.32 \\
 &= \mathbf{358533,926} \\
 &= 44,214,403,754
 \end{aligned}$$

$$\begin{aligned}
 (10) \quad & \text{Net delivered horse-power} \\
 &= \frac{9}{24 \times 60 \times 33000} \\
 &= \frac{44214403754}{24 \times 60 \times 33000} \\
 &= 930.43
 \end{aligned}$$

$$\begin{aligned}
 (11) \quad & \text{Steam used per net delivered horse power per hour(lb)} \\
 &= \frac{252415}{24 \times 930.43} \\
 &= 11.30
 \end{aligned}$$

$$\begin{aligned}
 (12) \quad & \text{I. H. P..} \\
 &= 993.58
 \end{aligned}$$

$$\begin{aligned}
 (13) \quad & \text{Mechanical Efficiency} \\
 &= \frac{(10) \quad 930.43}{(12) \quad 993.58} = .9392 \\
 &= 93.92 \%
 \end{aligned}$$

$$\begin{aligned}
 (14) \quad & \text{Duty per 100 pounds steam used (foot pounds)} \\
 &= \frac{(9)}{252415} \times 1000 \\
 &= \frac{44214403754}{252.415} \\
 &= 175165516
 \end{aligned}$$



The following is a record of the observations and the data and results derived therefrom.

### Table of Results

Number of Engine	E 2025
Date	10 - (1 - 2) - 08
Duration of trial (hrs).	24
Steam pressure at throttle (lbs)	141.6
" " on L. P. Jackets (lbs)	12.8
" " " reheater coils (lbs)	103.0
Vacuum in condenser (ins. mercury )	26.71
Barometer (lbs)	14.44
Balancing pressure pounds	106.0
Delivery pressure (guage reading ft.)	86.68
Elevation of gauge above Chicago Datum ( feet)	29.34
Elevation of water in wet-well below Chicago Datum (ft.)	7.3
Total head on pump (ft.)	123.32
Temperature of water pumped (° F )	60.7
Number of degrees superheat in steam at throttle (° F )	182.0
Total condensed steam from air pump and jackets (lbs)	252415.0
" revolutions of engine (24 hrs)	25605
Average revolutions of engine per minute	17.77
" length of stroke (ins)	61.487
" " " " (ft.)	5.124
" piston speed ft per minute	181.964
" plunger displacement per revolution (cu.ft.)	224.399



Average plunger displacement per rev.	(gals.)	1678.5
"	" " (lbs.)	14002.5
"	" 24 hrs.(cu.ft.)	5745736.0
"	" " " (gal)	42978105
"	" " " (lbs)	358533926
Net work delivered per 24 hours footpounds		44214403754
" delivered horse-power		930.43
Steam used per net delivered horse-power per hr.(lb.)		11.30
Indicated horse-power I.H.P.		993.58
Mechanical Efficiency		93.92
Duty per 1000 pounds steam used (foot pounds)		175165516



## Part V

### Conclusions


When this test was run it was purely commercial in character, the object being to determine whether or not the engine would develop the guaranteed duty, consequently the data necessary for a complete report as to heat balance etc. was not taken. We can, however, by taking the results of this test together with the tabulated list of previous tests, draw some interesting general conclusions. By comparing the duty of the tabulated list of pumps it will be seen that the pumps using superheated steam in every case develop a higher duty than those running on saturated steam. Another very noticeable feature is that the higher degree of superheat, within the limits of available data, the higher the duty delivered, as is shown by the curve, plate number 3. The points on this curve were taken from the data from the eight pumps included in the previous list, together with the results of the present test. It is to be expected that the points would not lie on a true curve as these pumps are located in different places, and were tested at different times under varying conditions, and no "correction curves" are presented whereby the data might be reduced to a common basis of pressure, speed, vacuum, and superheat. As stated above, it will be noticed that there is an increase of duty with an increase of superheat, but also, that the increment of increased duty grows smaller as the degree of superheat approaches the limit of the curve. This would indicate that there is an increase in economy of operation by



superheating up to 175°F after which the gain in duty practically ceases. The reason for this is probably that at the higher degrees of superheat, the steam goes through the three cylinders and is still slightly superheated when exhausted.

The fact that such a wide variation in conditions exists for the different points on the curve, and that there still exists this relation between superheat and duty, only goes to prove that the conclusions drawn may be relied upon.





**E 3025**  
 ERIE STATION  
 GENERAL ARRANGEMENT


FRONT ELEVATION  
 SIZE 7'-42" x 78" x 8" x 60"

SCALE 1/4" = 1'-0"  
 HENRY R WORTHINGTON  
 NEW YORK

**DR 30676**

PLATE I.






**E. 2025**  
 SPRINGFIELD AVENUE STATION  
 GENERAL ARRANGEMENT  
 SIDE ELEVATION.  
 SCALE: 1/4" = 1'-0"  
 DESIGNED BY  
 HENRY RWORTHINGTON  
 NEW YORK  
**DR 30677**



DIAGRAM  
 HENRY R. WORTHINGTON PRIME ENGINE - No. 1000  
 RIGHT SIDE - FOR END OF CYLINDER  
 SPRINGFIELD AVENUE STATION  
 CHICAGO



CURVE  
 SHOWING RELATION  
 BETWEEN  
 DUTY DEVELOPED AND SUPERHEAT  
 IN  
 PERFORMANCE  
 OF  
 WORTHINGTON HIGH DUTY PUMPING ENGINE

WORTHINGTON HIGH DUTY PUMPING ENGINE  
OF  
PERFORMANCE  
IN  
DUTY DEVELOPED AND SUPERHEAT  
SHOWING RELATION  
BETWEEN  
CURVE

DUTY IN MILLION FOOT-POUNDS 160 152 150 148 146 144 142 140 138 136 134 132 130 128 126 124 122 120 118 116 114 112 110 108 106 104 102 100 98 96 94 92 90 88 86 84 82 80 78 76 74 72 70 68 66 64 62 60 58 56 54 52 50

TEMPERATURE IN DEGREES F.




PLATE IV.


DIAGRAMS

HENRY R. WORTHINGTON PUMPING ENGINE NO. 2025.


RIGHT SIDE. TOP END OF CYLINDERS.

SPRINGFIELD AVENUE STATION.


CHICAGO.



HENRY R. WORTHINGTON, PUMPING ENGINE NO. 5052.  
 SPRINGFIELD AVENUE STATION.  
 CHICAGO.



DIAGRAMS  
HENRY R. WORTHINGTON PUMPING ENGINE NO. 2025.  
RIGHT SIDE. BOTTOM END OF CYLINDERS.  
SPRINGFIELD AVENUE STATION.  
CHICAGO.




30 60 90 120 150 180

COMBINED DIAGRAM

ATMOSPHERIC LINE

HYPERBOLIC CURVE



CHICAGO.

SPRINGFIELD AVENUE STATION.

RIGHT SIDE, BOTTOM END OF CYLINDERS

HENRY R. WEST, HENTON PUMPING ENGINE NO. 2052.

DIAGRAMS

PLATE IV.


DIAGRAMS

HENRY R. WORTHINGTON PUMPING ENGINE NO. 2025.

LEFT SIDE, TOP END OF CYLINDERS,


SPRINGFIELD AVENUE STATION,

CHICAGO.



COMBINED DIAGRAM

DIAGRAMS  
HENRY R. WORTHINGTON PUMPING ENGINE NO. 5052  
LEFT SIDE, TOP END OF CYLINDERS,  
SPRINGFIELD AVENUE STATION,  
CHICAGO.




DIAGRAMS

HENRY R. WORTHINGTON PUMPING ENGINE No. 2025.


LEFT SIDE. BOTTOM END OF CYLINDERS.

SPRINGFIELD AVENUE STATION.

CHICAGO.



DIAGRAMS  
HARRY WORTHINGTON PUMPING ENGINE NO. 2058.  
LEFT SIDE, BOTTOM END OF CYLINDERS.  
SPRINGFIELD AVENUE STATION  
CHICAGO.





1. The first part of the document discusses the importance of maintaining accurate records of all transactions. It emphasizes that proper record-keeping is essential for the transparency and accountability of the organization. This section also outlines the various methods used to collect and analyze data, ensuring that the information is reliable and up-to-date.

2. The second part of the document focuses on the implementation of these practices across different departments. It provides a detailed overview of the roles and responsibilities of each team, as well as the specific steps required to ensure compliance with the established protocols. This section also includes a timeline for the implementation process, highlighting key milestones and deadlines.

3. The third part of the document addresses the challenges and risks associated with the implementation of these practices. It identifies potential obstacles, such as resistance to change or limited resources, and provides strategies to mitigate these risks. This section also discusses the importance of ongoing monitoring and evaluation to ensure that the practices remain effective and relevant over time.

4. The fourth part of the document concludes with a summary of the key findings and recommendations. It reiterates the importance of maintaining accurate records and implementing these practices consistently across all departments. The document also provides a final timeline for the implementation process, ensuring that all necessary steps are completed by the specified deadline.

1. The first part of the document discusses the importance of maintaining accurate records of all transactions. It emphasizes that proper record-keeping is essential for the transparency and accountability of the organization. This section also outlines the various methods used to collect and analyze data, ensuring that the information is reliable and up-to-date.

2. The second part of the document focuses on the implementation of these practices across different departments. It provides a detailed overview of the roles and responsibilities of each team, as well as the specific steps required to ensure compliance with the established protocols. This section also includes a timeline for the implementation process, highlighting key milestones and deadlines.

3. The third part of the document addresses the challenges and risks associated with the implementation of these practices. It identifies potential obstacles, such as resistance to change or limited resources, and provides strategies to mitigate these risks. This section also discusses the importance of ongoing monitoring and evaluation to ensure that the practices remain effective and relevant over time.

4. The fourth part of the document concludes with a summary of the key findings and recommendations. It reiterates the importance of maintaining accurate records and implementing these practices consistently across all departments. The document also provides a final timeline for the implementation process, ensuring that all necessary steps are completed by the specified deadline.

Card No.	Bottom Top	Time	Mean Ordinate	M.E.P.	I.H.P.	Total I.H.P.	Mean Ordinate	M.E.P.	I.H.P.	Total I.H.P.	Mean Ordinate	M.M.P.	I.H.P.	Total I.H.P.	I.H.P. of Engine
16	P	8:00 P.M.	.832	66.6	104.4	209.7	.875	17.5	66.0		.697	6.97	86.8		486.6
	P		.840	67.2	105.3		.770	15.4	58.1	124.1	.530	5.30	66.0	152.8	
17	T		.842	67.4	105.6		.852	17.1	64.4		.700	7.00	87.2		493.3
	B	8:30 P.M.	.825	66.0	103.4	209.0	.885	17.7	66.7	131.1	.530	5.30	66.0	153.2	
	T		.850	68.0	106.5		.742	14.8	56.0		.705	7.05	87.2		496.7
18	B	9:00 "	.857	68.6	107.4	213.9	.917	18.3	69.2	125.2	.565	5.65	70.4	157.6	
	T		.866	69.2	108.4		.827	16.5	62.4		.700	7.00	87.2		
19	B	9:30 "	.840	67.2	105.3	213.7	.860	17.2	64.9	127.3	.562	5.62	70.0	157.2	498.2
	T		.852	68.2	106.8		.850	17.0	64.2		.700	7.00	87.2		
20	B	10:00 "	.857	68.6	107.4	214.2	.895	17.9	67.5	131.7	.562	5.62	70.0	157.2	503.1
	T		.867	69.3	108.5		.920	18.4	69.4		.730	7.30	91.0		
21	B	10:30 "	.852	68.2	106.8	215.3	.860	17.2	64.9	134.3	.540	5.40	67.2	158.2	507.8
	T		.835	66.8	104.6		.855	17.1	64.5		.700	7.00	87.2		
22	B	11:00 "	.870	69.6	109.0	213.6	.930	18.6	70.2	134.7	.570	5.70	71.0	158.2	506.5
	T		.860	68.8	107.8		.840	16.8	63.4		.700	7.00	87.2		
23	B	11:30 "	.847	67.8	106.2	214.0	.915	18.3	69.0	132.4	.525	5.25	65.4	152.6	499.
	T		.857	68.6	107.4		.840	16.8	63.4		.715	7.15	89.1		
24	B	12- midnight	.850	68.0	106.5	213.9	.920	18.4	69.4	132.8	.565	5.65	70.4	159.5	506.2
	T		.925	74.0	115.9		.790	15.8	59.6		.710	7.10	88.4		
25	B	12:30 A.M.	.992	79.0	123.7	239.6	.552	11.1	41.7	101.3	.677	6.77	84.3	172.7	513.6
	T		.901	72.8	114.0		.792	15.8	59.7		.725	7.25	90.4		
26	B	1:00 "	.995	76.4	119.7	233.7	.560	11.2	42.3	102.0	.675	6.75	84.1	174.5	510.2
	T		.922	77.7	115.4		.835	16.7	63.0		.722	7.22	90.0		
27	B	1:30 "	.935	74.8	117.2	232.6	.550	11.0	41.5	104.5	.677	6.77	84.3	174.3	511.4
	T		.902	72.2	113.1		.790	15.8	59.6		.720	7.20	89.7		
28	B	2:00 "	.900	72.0	112.8	225.9	.562	11.2	42.4	102.0	.680	6.80	84.6	174.3	502.2
	T		.905	72.4	113.4		.812	16.2	61.3		.725	7.25	90.4		
29	B	2:30 "	.900	72.0	112.8	226.2	.555	11.1	41.9	103.2	.670	6.70	83.5	173.9	503.3
	T		.937	75.0	117.5		.837	16.7	63.1		.727	7.27	90.5		
30	B	3:00 "	.935	74.8	117.2	234.7	.585	11.7	44.1	107.2	.680	6.80	84.7	175.2	517.1



Card No.	Bottom Top	Time	Mean M.E.P.	I.H.P.	Total I.H.P.	Mean Ordinate	M.E.P.	I.H.P.	Total I.H.P.	I.H.P. of Engine
31	T	3:30	A.M. 70.8	110.9	223.6	.808	16.2	61.0		
	B		900 72.0	112.7		.565	11.3	42.7	103.7	169.4
32	T		857 68.6	107.4		.808	16.1	61.0		
	B	4:00	" 72.8	114.0	221.4	.585	11.7	44.1	105.1	170.4
	T		885 70.8	110.9		.832	16.7	63.2		
33	B	4:30	"		221.8	.545	10.9	41.1	104.3	171.4
	T		880 70.4	110.3		.847	16.9	63.9		
34	B	5:00	" 74.1	116.0	226.3	.580	11.6	43.8	107.7	170.3
	T		852 68.2	106.8		.850	17.0	64.2		
35	B	5:30	" 72.8	114.0	220.8	.587	11.7	44.3	108.5	169.2
	T		847 67.8	106.2		.808	16.1	61.0		
36	E	6:00	" 73.2	114.7	220.9	.565	11.3	42.6	103.6	165.9
	T		857 68.6	107.4		.832	16.6	62.8		
37	B	6:30	" 71.4	111.8	219.2	.568	11.4	42.9	105.7	168.4
	T		855 68.4	107.2		.812	16.2	61.2		
38	E	7:00	" 71.6	112.2	219.4	.557	11.2	42.1	103.3	166.6
	T		825 66.0	103.1		.845	16.9	63.8		
39	B	8:00	" 65.6	99.6	203.0	.862	17.2	65.0	128.8	150.1
	T		823 65.9	103.2		.847	16.9	63.9		
40	E	8:30	" 68.0	106.5	209.7	.891	17.8	67.2	131.1	147.7
	T		837 66.9	104.8		.870	17.4	65.6		
41	B	9:00	" 68.0	106.5	211.3	.920	18.4	69.4	135.0	148.5
	T		827 66.1	103.6		.880	17.6	66.4		
42	B	9:30	" 66.8	104.7	208.3	.920	18.4	69.4	135.8	147.0
	T		830 66.4	104.0		.852	17.0	64.3		
43	B	10:00	" 65.8	103.1	207.1	.932	18.6	70.3	134.6	150.3
	T		840 67.2	105.2		.837	16.7	63.2		
44	B	10:30	" 66.9	104.8	210.0	.925	18.5	69.8	133.0	150.3
	T		837 66.9	104.8		.872	17.4	65.8		
45	B	11:00	" 66.0	103.4	208.6	.937	18.7	70.7	136.5	147.9
	T		825 66.8	104.6		.860	17.2	64.9		
46	B	11:30	" 67.4	105.5	210.1	.925	18.5	69.8	134.7	148.4
	T		800 64.0	100.2		.835	16.7	63.0		
47	B	1:00	P.M. 66.2	103.6	213.8	.935	18.7	70.6	133.6	146.3



Card No.	Bot-Time tom Top	Mean Ordinate	M.E.P.	I.H.P.	Total I.H.P.	Mean Ordinate	M.E.P.	I.H.P.	Total I.H.P.	I.H.P. of Engine
48	T B 1:30 P. M.	.827 .827 .827	66.2 66.2 66.2	103.6 103.6 103.6	207.2	.830 .960 .835	16.6 19.2 16.7	62.6 72.4 63.2	135.0	84.7 60.6 84.1
49	T B 1:30 "	.833 .825 .832	66.6 66.0 66.5	104.3 103.4 104.1	207.9	.747 ..813 .916	14.9 16.4 18.3	56.4 61.8 69.2	119.6	65.4 88.0 65.0
50	T B 1:45 "									

### Observers

C. B. Nolte - High Pressure Cylinder  
 Paul Burke - Intermediate Pressure Cylinder  
 E. C. Mc Millan - Low Pressure Cylinder

Cards	1	-	12	were taken from left side of engine
"	12	-	24	" right "
"	24	--	38	" left "
"	38	-	50	" right "

Average I.H.P. for left side of engine = 500.00  
 " I.H.P. " right " " = 493.58  
 Total average I.H.P. for engine = 993.58



Duty Test.  
Springfield Ave. Pumping Station.

Pump No. E 2025  
Oct. 1 & 2, 1908.

No. of read- ings	Time	Engine Log No. I		Gauges			Temperatures	
		Revolution Counter	Counter Rev. pr. inter val	Steam of en gine	Vol.	Disch water pres.	Wall level of en gine	Steam well
1	1.45	09317774.0		146.5	26.6	85	7.75	529 62
2	2.00	09318027.0	263.0	146.0	26.6	83	7.75	528 61
3	2.15	09318299.0	262.0	146.5	26.6	85	8.35	529 61
4	2.30	09318562.5	263.5	150.0	26.6	85	8.20	543 61
5	2.45	09318025.0	262.5	149.6	26.5	85	8.07	548 61
6	3.00	09319085.0	260.0	145.5	26.6	84	7.43	547 61
7	3.15	09319343.0	258.0	147.5	27.0	86	8.08	548 61
8	3.30	09319606.0	263.0	147.0	26.6	86	7.98	548 61
9	3.45	09319871.0	265.0	150.0	26.5	86.5	8.23	542 60
10	4.00	09320138.0	267.0	150.5	26.5	89	8.05	544 60
11	4.15	09320402.5	264.5	151.0	26.5	88	8.03	550 60
12	4.30	09320665.5	263.0	148.0	26.5	87	7.84	554 61
13	4.45	09320928.6	263.0	150.0	26.4	88.5	7.90	554 60
14	5.00	09321198.5	270.5	149.0	26.3	86	8.00	544 61
15	5.15	09321472.0	273.5	146.0	26.4	84.5	7.83	540 61
16	5.30	09321742.5	270.5	145.0	26.6	85	7.75	540 60
17	5.45	09322011.0	267.5	146.0	26.6	85	7.80	542 60
18	6.00	09322275.0	264.0	146.0	26.6	85	7.78	542 60
19	6.15	09322545.5	270.5	147.5	26.6	85	7.74	552 60
20	6.30	09322819.5	274.0	147.0	26.7	85.5	7.48	550 60
21	6.45	09323090.5	271.0	145.0	26.7	84	7.41	550 61
22	7.00	09323365.0	274.5	148.0	26.7	85	7.50	555 61
23	7.15	09323645.0	280.0	150.0	26.8	84	7.40	560 60
24	7.30	09323913.0	268.0	150.0	26.7	86	7.50	558 60
25	7.45	09324186.5	273.5	151.0	26.7	86.5	7.76	560 61
26	8.00	09324458.5	272.0	148.	26.6	88	7.40	542 61
27	8.15	09324727.5	269.0	147	26.7	85.5	7.40	548 61
28	8.30	09324991.5	264.0	145	26.7	87	7.40	550 61
29	8.45	09325256.0	264.5	145	26.7	86	7.40	548 60
30	9.00	09325517.5	261.5	147	26.7	88.5	7.42	550 61
31	9.15	09325782.0	264.5	145	26.7	86.5	7.40	542 60
32	9.30	09326045.5	263.5	143	26.6	86.5	7.40	544 61
33	9.45	09326307.5	262.5	147	26.6	88	7.40	544 61
34	10.00	09326571.0	263.5	145	26.7	88	7.40	542 61
35	10.15	09326830.5	259.5	147	26.7	88	7.40	547 61
36	10.30	09327089.5	259.0	150	26.6	89.5	7.40	544 61
37	10.45	09327347.5	258.0	146	26.6	89.5	7.40	540 61
38	11.00	09327607.5	260.0	149	26.6	88.5	7.40	543 61
39	11.15	09327874.5	267.0	146	26.6	88	7.40	544 61
40	11.30	09328138.0	263.5	148	26.6	89	7.40	540 61
41	11.45	09328404.0	266.0	149	26.6	89	7.40	536 61
42	12.00	09328668.0	264.0	147	26.6	89	7.40	528 61
43	12.15	09328933.5	265.5	149	26.4	89	7.40	534 61
44	12.30	09329201.0	267.5	149	26.4	89	7.40	544 61
45	12.45	09329471.0	270.0	146	26.9	89	7.40	548 61
46	1.00	09329732.0	261.0	149	26.9	89	7.40	550 61



## Duty Test (cont)

Springfield Ave. Pumping Station

Pump No. E 2025

Oct. 1 &amp; 2, 1908.

No. Of read ings	Time	Engine Log No. 1		Gauges			Temperatures	
		Revolution Counter	Rev. pr. interval	Steam of en gine	Vac Water pres.	Disch level	Steam of en gine	Well
47	1.15	09329999.0	267.0	146	26.9 89	7.40	543	61
48	1.30	09330264.0	265.0	149	26.9 89	7.50	540	61
49	1.45	09330526.0	262.0	145	26.8 89	7.50	538	61
50	2.00	09330780.0	254.0	144	26.9 89	7.50	537	61
51	2.15	09331039.5	259.5	145	26.9 89	7.50	538	61
52	2.30	09331293.0	253.5	145	26.9 89	5.25	538	61
53	2.45	09331552.0	259.0	145	26.9 89	5.20	536	60
54	3.00	09331812.0	265.0	146	26.8 89	5.80	540	61
55	3.15	09332083.5	266.5	146	26.8 89	5.29	540	60
56	3.30	09332340.0	256.5	145	26.8 89	5.24	529	61
57	3.45	09332599.0	259.0	148	26.8 89	5.70	532	61
58	4.00	09332862.0	263.0	150	26.7 89	5.60	540	61
59	4.15	09333121.0	259.0	147	26.7 89	5.25	538	61
60	4.30	09333376.5	255.5	147	26.7 89	5.58	533	61
61	4.45	09333636.0	259.5	145	26.8 89.0	5.35	535	61
62	5.00	09333898.0	262.0	146	26.7 89.	5.45	536	61
63	5.15	09334170.0	272.0	145	26.8 87	5.70	536	61
64	5.30	09334438.0	268.0	148	26.8 88	6.30	532	61
65	5.45	09334708.0	270.0	142.5	26.8 86.5	6.50	542	61
66	6.00	09334976.0	268.0	145	26.8 86.5	6.00	546	61
67	6.15	09335249.0	273.0	145	26.8 86.0	7.01	544	61
68	6.30	09335532.0	283.0	148	26.8 85.5	7.56	542	61
69	6.45	09335812.5	280.5	146	26.8 84.0	7.89	535	61
70	7.00	09336091.0	278.5	145	26.8 84.5	7.84	540	61
71	7.15	09336355.0	264.0	145	26.9 84.5	7.98	532	61
72	7.30	09336628.0	273.0	145	26.8 85.0	8.05	530	61
73	7.45	09336894	266.0	145	26.8 85.0	8.33	543	61
74	8.00	09337164	270.0	148	26.8 86.0	8.72	546	61
75	8.15	09337433	269.0	147	26.8 85.0	8.60	542	61
76	8.30	09337707	274.0	146	26.8 85.0	8.40	547	60
77	8.45	09337979.0	272.0	146	26.8 85.0	8.51	540	60
78	9.00	09338252.0	273.0	147	26.8 85.5	8.60	543	60
79	9.15	09338522.0	270.0	147	26.8 85.5	8.52	548	60
80	9.30	09338796.0	274.0	145	26.8 85.5	8.50	549	60
81	9.45	09339073.0	277.0	147	26.8 85.5	8.49	544	60
82	10.00	09339346.0	273.0	145	26.8 85.5	8.40	546	60
83	10.15	09339614.0	268.0	146	26.8 85.5	8.30	538	60
84	10.30	09339883.0	269.0	145	26.8 85.5	8.34	548	60
85	10.45	09340154.0	271.0	149	26.8 86.5	8.65	561	60
86	11.00	09340426.0	272.0	143	26.8 85.5	8.05	562	60
87	11.15	09340697.0	271.0	147	26.8 86.0	8.39	554	60
88	11.30	09340968.0	271.0	147	26.8 85.5	8.35	552	60
89	11.45	09341241.0	273.0	146	26.8 85.5	8.33	550	61
90	12.00	09341515.0	274.0	148	26.8 85.5	8.52	546	61
91	12.15	09341781.0	266.0	146	26.8 85.5	8.25	545	61
92	12.30	09342049.0	269.0	147	26.8 85.5	8.12	546	61
93	12.45	09342312.0	263.0	143	26.8 85.0	8.00	536	60



## Duty Test (cont)

Springfield Ave. Pumping Station

Pump No. E 2025

No. of read- ings	Time	Revolution Counter	Engine Log		No. I Gauges		Temperatures		
			Rev. pr. interval	Steam of en gine	Voc.	Disch. water pres.	Well level	Steam of en gine	Well
94	1.00	09342584.0	272.0	150	26.8	85.5	8.48	551	60
95	1.15	09342848.0	264.0	149	26.8	85.5	8.38	548	61
96	1.30	09343114.0	266.0	151	26.8	86.0	8.60	550	61
97	1.45	09343379.0	265.0	148	26.8	85.5	8.32	552	61
			266.6	147	26.7	86.68	7.45	543	60.68

Correction due to  
13.48 ft. water col. on Steam ga. 5.

Av. Steam Pres.  $\frac{5.84}{141.16}$

Log of Observers :

1.45 P.M.	-	6.00 P M	Haynes, Golden
6.00	-	6.30	Golden -----
6.30	-	7.15	Haynes -----
7.15	-	9.00	Haynes Golden
9.00	-	4.30 A.M.	Martin Halpin
4.30 A.M.	-	6.45	Martin Nicholson
6.45	-	7.30	Martin -----
7.30	-	8.30	Martin Nicholson
8.30	-	11.15	Martin Nicholson
11.15	-	12.00	Martin -----
12.00	-	12.35 P.M.	Nicholson ----
12.35 P.M.	-	1.45	Martin, Nicholson



## Duty Test

Springfield Ave. Pumping Station

Pump No. E 2025

Oct. 12 2, 1908.

No. of Time read-ings	Engine Log No. 2							Stroke Shortag			
	Receivers		Gauges		L.P. Jack et	Bal ance Pres.	Acc. Back Pres.	No.1 side		No.2 side	
	1st.	2nd.	Reheat-er Coil					Up	Down	Up	Down
1	1.45	29	.5	91	17.5	101	13.5	0	1/8	0	1/8
2	2.00	29	.5	90	17.5	107	13.5	1/8	3/4	1/8	5/8
3	2.15	31	1.2	90	18	107	13.7	0	1/2	0	1/4
4	2.30	30	1.2	102	16	107	13.4	0	1/8	0	1/8
5	2.45	30	1.2	103	15	106	13.3	1/8	1/8	1/8	1/8
6	3.00	29	1.2	103	13	106	13.7	0	1/8	0	1/8
7	3.15	31	1.2	103	14	106	13.7	0	1/8	0	1/4
8	3.30	31	1.2	103	13	105	13.7	1/4	1/8	1/4	1/8
9	3.45	32	1.2	102	12.5	106	13.6	1/8	1/8	0	1/8
10	4.00	32	2.0	105	12	105	13.6	1/4	1/8	1/8	1/4
11	4.15	31.5	2.0	106	12	105	13.7	1/4	1/8	1/8	1/4
12	4.30	31	1.2	106	12	104	13.7	1/4	1/4	1/4	3/8
13	4.45	32	1.5	106	12	104	13.6	1/4	1/8	1/4	3/8
14	5.00	31	1.5	105	12	104	13.6	1/4	1/8	1/4	1/4
15	5.15	31	1.5	101	12	105	13.5	1/4	1/4	1/8	1/4
16	5.30	30	1.5	103	12	105	13.5	3/8	1/4	3/8	1/4
17	5.45	30	1.2	103	12	105	13.6	1/4	1/4	1/4	1/8
18	6.00	30	1.5	102	12	103	13.6	3/8	1/4	3/8	1/4
19	6.15	30	1.5	105	12	104	13.6	3/8	1/8	1/4	1/8
20	6.30	31	1.5	105	12	106	13.7	3/8	1/8	1/4	1/8
21	6.45	30	1.5	102	12	105	13.7	1/4	1/8	1/8	1/8
22	7.00	31	1.5	103	12	105	13.7	1/4	1/8	1/4	1/8
23	7.15	30	1.5	103	12	111	13.5	1/4	1/8	1/4	1/8
24	7.30	31	1.5	104	12	110	13.7	1/4	1/8	1/4	1/8
25	7.45	30	1.5	103	12	110	13.7	1/8	1/4	1/8	1/4
26	8.00	31	1.5	105	12	105	13.5	1/8	1/8	1/8	1/4
27	8.15	31	1.5	104	12	107	13.5	0	3/8	1/8	1/4
28	8.30	30	1.5	103	12	110	13.7	0	3/8	0	1/4
29	8.45	30	1.5	104	12	108	13.6	0	3/8	0	3/8
30	9.00	30	1.5	105	12	109	13.7	0	1/4	0	0
31	9.15	30.0	1.5	103	12	110	13.8	0	3/8	0	1/4
32	9.30	29.5	1.5	103	12	113	13.6	0	1/8	0	1/4
33	9.45	30	1.5	104	12	114	14.2	1/8	3/8	0	1/8
34	10.00	30	1.5	104	12	108	14.2	1/8	1/4	0	0
35	10.15	30	1.5	106	12	107	14.8	1/8	1/4	1/8	1/8
36	10.30	30	1.5	106	12	106	14.5	0	1/4	1/8	1/8
37	10.45	30	1.5	106	12	108	13.9	0	1/8	0	1/4
38	11.00	30	2.0	106	12	106	14.2	0	1/4	0	1/8
39	11.15	30	2.0	105	12	106	14.0	0	1/4	0	1/4
40	11.30	30	2.0	105	12	107	14.0	0	1/4	0	1/4
41	11.45	31	2.0	105	12	106	14.0	0	1/4	0	1/4
42	12.00	31	2.0	105	12	106	14.0	0	1/4	0	1/4
43	12.15	31	2.0	105	12	106	14.0	0	1/8	0	1/4



## Duty Test (cont)

Springfield Ave. Pumping Station

Pump No. E 2025

Oct. 1 &amp; 2, 1908.

## Engine Log. No. 2

No. of Time Read- ing		Receivers		Gauges	L.P. Jack et	Bal ance Pres	Acc. Back Pres.	Stroke No. 1 Up	Shortage		
		1st	2nd	Reheat- er Coils					Side Down	No. 2 Up Down	
44	12.30	31	2.0	104	12	106	14.6	0	1/8	0	1/8
45	12.45	31	2.0	104	12	107	14.3	0	1/4	0	1/4
46	1.00	31	2.0	105	12	107	14.8	0	1/4	0	1/8
47	1.15	31	2.0	106	12	106	14.5	1/8	1/4	1/4	3/8
48	1.30	31	1.7	106	12	106	14.2	0	1/8	0	1/8
49	1.45	30	1.7	105	12	106	13.9	0	1/4	1/8	3/8
50	2.00	30	1.7	104	12	106	13.8	0	1/4	0	3/8
51	2.15	30	1.7	104	11.5	106	13.9	0	1/8	1/8	3/8
52	2.30	30	1.7	104	11.5	105	14.3	0	0	1/8	1/4
53	2.45	30	1.7	103	11.5	105	14.4	1/8	1/8	0	1/8
54	3.00	32	1.8	104	11.3	108	15.3	0	1/8	0	3/8
55	3.15	31	1.2	105	11.0	107	14.9	0	1/4	0	3/8
56	3.30	30	1.3	103	11.0	107	14.2	0	1/8	1/8	1/4
57	3.45	31	1.3	104	11.0	106	14.6	0	1/8	0	1/2
58	4.00	31	1.3	105	11.0	106	14.9	0	3/8	1/8	1/8
59	4.15	31	1.1	104	11.0	106	14.9	0	1/4	1/8	1/8
60	4.30	31	1.0	104	11.0	105	14.2	0	1/4	1/8	1/4
61	4.45	30	1.0	102	11.5	105	14.6	0	1/4	1/8	1/4
62	5.00	31	1.1	101	11.5	105	15.0	0	1/4	0	1/4
63	5.15	31	1.0	100	11.5	107	14.8	0	3/8	0	3/8
64	5.30	31.5	1.0	100	11.5	106	15.0	0	1/4	0	1/4
65	5.45	30	1.0	100	11.7	106	14.7	0	1/8	1/8	1/4
66	6.00	30	1.0	100	12.0	107	14.8	0	1/8	1/8	0
67	6.15	30	1.0	100	12.0	107	14.4	0	1/4	0	1/4
68	6.30	32	1.0	100	12.0	107	14.3	1/8	1/4	0	1/4
69	6.45	32	1.0	100	12.0	107	13.8	0	1/8	0	1/8
70	7.00	31	1.0	100	12.0	106	13.8	0	1/4	0	1/8
71	7.15	31	1.0	100	12.0	106	14.2	0	1/8	0	1/4
72	7.30	31	1.0	100	11.8	106	13.6	0	3/8	0	1/4
73	7.45	31	1.0	100	12.0	106	13.7	0	1/8	0	0
74	8.00	32	2.5	100	12.0	106	13.4	0	1/8	0	0
75	8.15	32	2.0	100	12.0	105	13.6	0	1/8	0	0
76	8.30	31	2.0	100	12.0	105	13.6	0	0	0	0
77	8.45	30	1.3	100	12.0	105	13.5	0	1/8	0	1/8
78	9.00	31	1.3	100	12.0	105	13.8	0	1/8	0	1/8
79	9.15	31	1.8	100	12.0	104	13.8	0	0	0	0
80	9.30	31	1.3	100	12.0	104	14.2	0	0	0	1/8
81	9.45	32	2.0	100	12.0	104	14.1	0	1/8	0	1/8
82	10.00	31	1.3	100	12.0	104	14.0	0	1/8	0	1/8
83	10.15	31	1.3	100	12.0	104	14.0	0	0	0	0
84	10.30	31	1.3	100	12.0	104	14.0	1/8	0	0	0
85	10.45	32	1.3	102	12.5	104	14.5	1/8	1/4	0	1/8
86	11.00	31	1.3	100	12.5	105	14.3	1/8	1/8	1/8	1/4
87	11.15	32	1.3	102	12.5	105	14.0	0	0	0	1/8
88	11.30	31	1.3	102	12.5	105	13.9	1/8	1/4	0	1/8



Duty Test (cont)  
Springfield Ave. Pumping Station

Pump E 2025  
Oct. 2, 1908

No. of Time read- ings			Engine Log No. 2						Stroke Shortage		
	Receivers		Gauges								
	1st	2nd	Reheat er coils	J.P. Jack et	Bal ance Pres.	Acc. Back Pres.	No. 1 Up	side Down	No. 2 Up	sid Down	
89.	11.45	31	1.3	102	12.5	105	13.8	0	1/8	0	1/8
90	12.00	31	1.3	103	12.5	104	13.8	1/8	1/4	1/8	1/4
91	12.15	31	1.3	103	13.0	104	13.5	0	1/8	1/8	1/4
92	12.30	31	2.0	103	13.0	104	13.5	1/8	1/8	1/8	1/4
93	12.45	30	1.5	101	13.0	104	13.6	0	1/8	0	1/8
94	1.00	31	1.3	103	13.0	104	13.5	0	1/8	0	1/8
95	1.15	31	1.3	103	13.0	104	13.5	0	1/8	0	0
96	1.30	31	1.5	105	13.0	102	14.0	1/8	1/4	0	0
97	1.45	31	1.5	105	13.0	104	13.9	0	1/4	0	0
Average		31.0	1.46	103	12.8	106	14.1			0.513	

Log of Observers.

1.45 P.M.	-	5.00 P.M.	Palmer, McCarty
5.00 P.M.	-	6.00 P.M.	McCarty, Olsen
6.00 P.M.	-	6.30 P.M.	McCarty -----
6.30 P.M.	-	7.10 P.M.	Olsen
7.10 P.M.	-	9.00 P.M.	Palmer, McCarty
9.00 P.M.	-	4.30 A.M.	Persons, Heyne
4.30 A.M.	-	6.45 A.M.	Persons, O'Bryne
6.45 A.M.	-	7.30 A.M.	O'Bryne -----
7.30 A.M.	-	8.30 A.M.	Persons
8.30 A.M.	-	12.00 A.M.	O'Bryne
12.00 A.M.	-	12.40 P.M.	Persons -----
12.40 P.M.	-	1.45 P.M.	Persons, O'Bryne



## Duty Test

Springfield Ave. Pumping Station

Pump No. E 2025

Oct. 1, 1908.

Log of Condensed Steam										
No. of read'g	Temp. don- den sed steam	Time	Barrel No. 1			Barrel No. 2				
			Tare	Gross	Net	Time	Tare	Gross	Net	
63 F	1 .55 P.M.	355	1244	889	1.50	341	1262	921		
63 F	2.05 " "	376	1332	956	2.00	320	1131	811		
63 F	3.47 " "	347	1183	836	2.10	336	1234	898		
63 F	2.25 " "	358	1236	878	2.20	313	1278	965		
63 F	2.35 " "	358	1317	959	2.30	313	1200	887		
70 F	2.45 " "	353	1030	677	2.40	321	1206	885		
63 F	2.55 " "	430	1293	863	2.50	424	1266	842		
63 F	3.05 " "	437	1326	889	3.00	416	1206	790		
63 F	3.15 " "	448	1286	838	3.10	385	1227	842		
63 F	3.25 " "	447	1344	897	3.20	443	1376	933		
63 F	3.35 " "	445	1358	913	3.30	446	1291	845		
70 F	3.45 " "	445	1352	907	3.40	466	1336	870		
63 F	3.55 " "	438	1337	899	3.50	444	1351	907		
63 F	4.05 " "	426	1362	936	4.00	425	1339	914		
68 F	4.15 " "	463	1337	874	4.10	431	1292	861		
68 F	4.25 " "	444	1297	853	4.20	436	1387	951		
68 F	4.35 " "	443	1390	947	4.30	424	1250	826		
70 F	4.45 " "	437	1250	813	4.40	431	1334	903		
70 F	4.55 " "	450	1347	897	4.50	426	1400	974		
69 F	5.05 " "	449	1460	1011	5.00	451	1284	833		
68 F	5.15 " "	444	1272	828	5.10	433	1315	882		
71 F	5.25 " "	442	1298	856	5.20	425	1383	958		
68 F	5.35 " "	459	1429	970	5.30	441	1216	875		
67 F	5.45 " "	447	1220	773	5.40	444	1292	848		
70 F	5.55 " "	450	1265	815	5.50	434	1379	945		
67 F	6.05 " "	446	1367	921	6.00	436	1180	744		
74 F	6.15 " "	446	1214	768	6.10	428	1347	919		
68 F	6.25 " "	446	1368	922	6.20	427	1370	943		
65 F	6.35 " "	441	1348	907	6.30	431	1228	797		
68 F	6.45 " "	446	1239	793	6.40	424	1310	886		
65 F	6.55 " "	451	1384	933	6.50	427	1338	911		
65 F	7.05 " "	438	1297	859	7.00	430	1231	811		
72 F	7.15 " "	380	1214	834	7.10	326	1293	967		
68 F	7.25 " "	365	1404	1039	7.20	325	1297	972		
67 F	7.35 " "	380	1312	932	7.30	332	1103	771		
70 F	7.45 " "	377	1229	852	7.40	319	1253	934		
65 F	7.55 " "	367	1370	1003	7.50	325	1251	926		
63 F	8.05 " "	433	1427	994	8.00	375	1162	787		
64 F	8.15 " "	455	1252	797	8.10	432	1254	822		
65 F	8.25 " "	454	1378	924	8.20	424	1370	946		
65 F	8.35 " "	452	1374	922	8.30	427	1192	765		
63 F	8.45 " "	448	1280	832	8.40	381	1332	951		
60 F	8.55 " "	455	1312	857	8.50	418	1309	891		



## Duty Test (cont)

Springfield Ave. Pumping Station

Pump No. E 2025

Oct. 1, 1908.

		Log of Condensed Steam							
No. of read'g	Temp. don- dens ed steam	Time	Barrel No. 1			Barrel No. 2			
			Tare	Gross	Net	Time	Tare	Gross	Net
69 F	9.05 P.M.		442	1282	840	9.00	424	1322	898
67 F	9.15 "	"	456	1341	885	9.10	431	1353	922
70 F	9.25 "	"	451	1387	936	9.20	411	1386	975
68 F	9.35 "	"	450	1351	901	9.30	402	1150	748
71 F	9.45 "	"	447	1261	814	9.40	435	1377	942
65 F	9.55 "	"	451	1400	949	9.50	435	1319	884
68 F	10.05 "	"	451	1318	867	10.00	430	1272	842
69 F	10.15 "	"	451	1318	860	10.10	438	1335	897
69 F	10.25 "	"	453	1360	907	10.20	375	1362	987
66 F	10.35 "	"	453	1353	900	10.30	445	1200	755
70 F	10.45 "	"	451	1255	804	10.40	410	1418	1008
71 F	11.05 "	"	478	1335	857	10.50	433	1327	894
71 F	11.05 "	"	453	1470	1017	11.00	432	1222	790
69 F	11.05 "	"	455	1217	762	11.10	423	1335	912
64 F	11.25 "	"	445	1267	822	11.20	438	1360	922
72 F	11.35 "	"	458	1355	897	11.30	433	1176	743
71 F	11.45 "	"	442	1481	1039	11.40	423	1336	913
73 F	11.55 "	"	449	1356	907	11.50	425	1316	891
68 F	12.05 "	"	445	1351	906	12.00	434	1352	918
68 F	12.15 "	"	454	1340	886	12.10	423	1390	967
64 F	12.25 "	"	440	1379	939	12.20	430	1415	985
65 F	12.35 "	"	441	1347	906	12.30	405	1214	809
67 F	12.45 "	"	453	1337	884	12.40	430	1335	905
70 F	12.55 "	"	449	1331	882	12.50	422	1258	836
64 F	1.05 "	"	447	1325	878	1.00	425	1362	937
63 F	1.15 "	"	441	1360	919	1.10	427	1407	980
61 F	1.25 "	"	440	1300	860	1.20	436	1358	922
61 F	1.35 "	"	437	1214	777	1.30	425	1315	890
66 F	1.45 "	"	441	1144	703	1.40	432	1108	676
60 F	1.55 "	"	439	1185	746	1.50	425	1121	696
64 F	2.05 "	"	434	1167	733	2.00	426	1043	617
70 F	2.15 "	"	456	1245	789	2.10	412	1349	937
65 F	2.25 "	"	442	1274	832	2.20	424	1314	890
61 F	2.35 "	"	447	1392	945	2.30	423	1208	785
65 F	2.45 "	"	444	1202	758	2.40	394	1207	813
70 F	2.55 "	"	443	1345	902	2.50	427	1288	861
62 F	3.05 "	"	445	1467	1022	3.00	429	1325	896
68 F	3.15 "	"	449	1286	837	3.10	437	1299	862
70 F	3.25 "	"	459	1287	828	3.20	440	1352	912
60 F	3.35 "	"	451	1420	969	3.30	445	1233	788
70 F	3.45 "	"	444	1309	865	3.40	432	1267	835
69 F	3.55 "	"	438	1290	852	3.50	432	1354	922
65 F	4.05 "	"	444	1260	816	4.00	438	1341	903
59 F	4.15 "	"	446	1257	811	4.10	426	1354	928
68 F	4.25 "	"	438	1229	791	4.20	430	1299	869



## Duty Test (cont)

Springfield Ave., Pumping Station

Pump No. E 2025  
Oct. 1st 1908

## Log of Condensed Steam

No. of read'g	Temp. con dens ed steam	Time	Tare	Gross	Net	Time	Tare	Gross	Net
66		4.35	439	1337	898	4.30	423	1272	849
70		4.45	454	1230	776	4.40	435	1300	860
68		4.55	446	1330	884	4.50	451	1320	865
68		5.05	418	1422	1004	5.00	430	1221	791
67		5.15	437	1232	795	5.10	437	1334	897
67		5.25	455	1330	875	5.20	437	1378	941
67		5.35	445	1387	942	5.30	430	1280	850
64		5.45	445	1283	838	5.40	395	1248	853
65		5.55	426	1355	929	5.50	433	1314	881
72		6.05	444	1334	890	6.00	432	1371	939
65		6.15	446	1265	819	6.10	431	1316	885
70		6.25	446	1357	911	6.20	423	1404	981
66		6.35	435	1411	976	6.30	422	1318	896
69		6.45	440	1320	880	6.40	424	1340	916
70		6.55	441	1442	1001	6.50	425	1297	872
65		7.05	445	1335	890	7.00	423	1225	802
69		7.15	438	1251	813	7.10	424	1266	842
65		7.25	447	1300	853	7.20	432	1405	973
67		7.35	443	1334	891	7.30	426	1283	857
65		7.45	450	1244	794	7.40	425	1294	869
60		7.55	451	1343	892	7.50	429	1280	861
65		8.05	388	1266	878	8.00	339	1223	884
75		8.15	382	1144	762	8.10	304	1236	932
64		8.25	421	1355	934	8.20	350	1266	916
63		8.35	439	1292	853	8.30	408	1273	865
65		8.45	436	1267	831	8.40	438	1365	927
65		8.55	445	1331	886	8.50	395	1387	992
64		9.05	446	1429	983	9.00	451	1239	788
66		9.15	452	1268	816	9.10	442	1315	873
68		9.25	449	1440	991	9.20	431	1403	972
71		9.35	448	1431	983	9.30	435	1229	794
71		9.45	453	1232	779	9.40	436	1376	940
65		9.55	450	1360	910	9.50	427	1330	923
66		10.05	430	1319	889	10.00	432	1210	778
67		10.15	447	1338	891	10.10	423	1220	797
67		10.25	453	1293	840	10.20	428	1377	950
65		10.35	463	1270	807	10.30	446	1227	781
69		10.45	446	1277	831	10.40	443	1294	851
66		10.55	452	1254	802	10.50	430	1468	1038
65		11.05	451	1464	1013	11.00	394	1196	802
65		11.15	449	1221	772	11.10	434	1272	838
66		11.25	450	1283	833	11.20	451	1455	1004
66		11.35	458	1488	1030	11.30	435	1182	747
65		11.45	447	1208	761	11.40	436	1323	887
65		11.55	454	1328	874	11.50	426	1455	1029



## Duty Test (cont)

Springfield Ave. Pumping Station

Pump No E 2025

Oct. 1, 1908

		Log of Condensed Steam							
No. of read'g	Temp. con den sed steam	Time	Barrel No. 1			Barrel No. 2			
			Tare	Gross	Net	Time	Tare	Gross	Net
72		12.05	441	1310	869	12.00	417	1273	856
68		12.15	446	1257	811	12.10	428	1330	902
70		12.25	440	1332	892	12.20	430	1405	975
64		12.35	442	1155	713	12.30	436	1249	813
64		12.45	442	1245	803	12.40	432	1361	929
64		12.55	446	1173	727	12.50	424	1365	941
65		1.05	438	1323	885	1.00	403	1328	925
63		1.15	442	1224	782	1.10	430	1286	856
60		1.25	459	1356	897	1.20	426	1453	1027
60		1.35	448	1505	1057	1.30	441	1200	759
65		1.45	445	1179	734	1.40	428	1258	830
Average 66.6									

Total Condensed Steam 252415 lbs.

## Observers

1.45 -	5.00	Boesch ,	Olsen
5.00 p	6.30	Boesch	Palmer
6.30 -	7.10		Palmer
7.10 -	8.40	Boesch	
8.40 -	8.45	Boesch	Akeson
8.45 -	4.30 A.M.	"	Akeson
4.30 -	6.45	Boesch	Carlson
6.45 -	7.30	Boesch	Carlson
7.30 -	8.30	Boesch	
8.30 -	11.15	Boesch	Carlson
11.15 -	11.55		Carlson
11.55 -	12.25	Boesch	
12.25 -	1.45	Boesch	Carlson





UNIVERSITY OF ILLINOIS-URBANA



3 0112 079825508